



Village of Sackets Harbor
Market Square Park REDI Improvements & Rehabilitation
REDI Asset No. SJ. 280
BCA Project No. 2020-027

Addendum No. 2
May 26, 2022

This addendum is hereby made part of the Contract Documents as though it were originally included therein and must be acknowledged by the bidder in the proper place on the bid form.

Project Manual

1. Reference Advertisement for Bids, paragraph 1, 'Sealed Bids for the construction of...':
 - a. DELETE '6/02/2022' and SUBSTITUTE the following '6/09/2022'.
2. Reference SECTION 03 3300, Paragraph 2.02.I, "Fiber Reinforcement...":
 - a. Under paragraph 2.02.I.1, after "Fiber Length: 0.25 inch", ADD "min."
 - b. Under paragraph 2.02.I.2, SUBSTITUTE paragraph "b." with:
"b. ABC Polymer Industries LLC; Fiberforce; <https://fiberforce.us/>
c. or approved equal"

Please see attached Request for Information (RFI) Question and Answer Log for RFI responses to date, 5.26.2022.

Respectfully Submitted,

BCA ARCHITECTS & ENGINEERS

Corey G. Reid, P.E
Principal/Civil Engineer

Status	RFI ID	Subject	Question	Answer	Closed
Closed	00001	Three questions on Sackets Harbor Redi Project	1.Refer to drawing S1-2 section EE take at the new poured in place retaining wall. There is no section EE should this reference section D on ST1-2?	Correct. Ignore section E-E on S1-2, reference section D on ST1-2. This discrepancy will also be rectified via addendum prior to bid.	5/12/2022
	00002	Three questions on Sackets Harbor Redi Project	2.) Refer to drawing S1-2 there is a note to provide new cable guardrail adjacent to the west end. Please provide a detail as to what is required for posts and cables.	Please refer to the guardrail details on the bottom of sheet D1-5. These depict the post and cables required in this project.	5/12/2022
	00003	Three questions on Sackets Harbor Redi Project	3.) Reference sheet ST1-2 please provide spacing for the W6x25 Vehicle rail support columns.	The W6x25 rail support columns are located 1'-0" inward from the ends of the retaining wall and spaced 6'-1 5/16" in-between (total of four W6x25 columns).	5/13/2022
	00004	Couple of questions on the Sackets project:	1. Refer to drawing S1-4 shows two flag poles. Can you provide a size or spec on what is desired here. 2. Refer to drawing S1-4 indicates two bike racks. Please provide a spec. on what is desired here.	Please disregard the previous answer and replace it with the following answer. Apologies for the mixed responses as we did not realize the flag pole had been specified on the electrical sheets. 1) For the flag poles, please refer to sheet E100, key note P19 for the flag pole make and model that were specified. Also please refer to the luminaire schedule on sheet E600 for the flag pole light make and model that were specified. 2) The two bike racks shall be 5-bike, single sided, powder coated steel, grid bike rack by Global Industrial, or approved equal.	5/23/2022
	00005	Chapin Tie-back anchors	1. Refer to drawing S2-1 shows 2'x4' tie back anchors. How long are each of the anchors?	The 2'x4' concrete deadman is continuous and runs parallel to the shoreline with an approximate length of 38'. The 1 1/2" diameter tieback anchors are approximately 30' long minimum.	5/23/2022
	00006	Flag poles & bike rack questions	Drawing S1-4 depicts new bike racks and Can-Am Flagpoles to be installed on the northside of west main street, however it appears that there are no details or specifications for these included in the bid documents. 1. Please provide the specifications for the desired products 2. Please provide the details for each item to include the foundation and/or attachment details.	1. For the flag poles, please refer to sheet E100, key note P19 for the flag pole that was specified. Also, please refer to the luminaire schedule on sheet E600 for the flag pole light that was specified. The two bike racks shall be 5-bike, single sided, powder coated steel, grid bike rack by Global Industrial, or approved equal. 2. Please refer to sheet E500 for the flag pole foundation detail. The bike racks are intended to be free-standing, so no foundation or attachment detail is available at this time.	5/23/2022

Total RFIs: 6