



Jefferson Community College
Athletic Turf Field Complex
Project No. 2019-085 - REBID

Addendum No. 1

July 5, 2022

This addendum is hereby made part of the Contract Documents as though it were originally included therein and must be acknowledged by the bidder in the proper place on the bid form.

Project Manual

1. **Reference Notice to Bidders, paragraph 1, 'Sealed bids for the construction...':**
 - A. **DELETE 'July 7, 2022' and SUBSTITUTE the following 'July 13, 2022'.**

2. **Reference SECTION 32 9200 ARTIFICIAL TURF**
DELETE all references to 'shock pad' in all portions of the specification.

3.07 , PARAGRAPH B

- A. **DELETE** Paragraph B in its entirety
 - i. **ADD** the following wording:
At the time of substantial completion, the average G-max rating must not exceed **125**. The average G-max must not exceed **165** at any time during the life of the warranty. The owner reserves the right to have the field tested for shock attenuation at it's own cost at anytime it deems necessary. If at anytime the G-max ranges reach unacceptable levels, it is the responsibility of the turf contractor to bring the field back into the required ranges at no cost to the owner.

Contract Drawings:

1. **Reference the Cover Sheet, General Note 33.**
 - A. **DELETE General Note 33 in its entirety.**

2. **Reference sheet C-300, Area Drain No. 2 (Inserted into Existing Storm Line).**
 - A. **DELETE label 'Area Drain No. 2' in its entirety.**
 - B. **ADD label 'Area Drain No. 3'.**

3. **Reference to Detail 4, Sheet C-602 – Slotted Trench Drain Detail;**
A. ***DELETE* Slotted Trench Drain Detail *in its entirety.***

Respectfully submitted,

BCA ARCHITECTS & ENGINEERS

A handwritten signature in black ink, appearing to read "Michael Altieri", with a long horizontal flourish extending to the right.

Michael D. Altieri, P.E.
Principal/Civil Engineer